Executive Summary of Environmental Impact Assessment Report of Orange Smart City, Pen Taluka, Raigad District





SUBMITTED TO

MAHARASHTRA POLLUTION CONTROL BOARD FOR PUBLIC HEARING.

PROJECT PROPONENT : ORANGE SMART CITY INFRASTRUCTURE PVT. LTD.

ENVIRONMENTAL CONSULTANT : BUILDING ENVIRONMENT (INDIA) PVT. LTD.



FEBRUARY 2017

1.0 Project Context

The 'Orange Smart City Infrastructure Pvt. Ltd.' (OSCIPL), a public registered company intends to develop 'Orange Smart City' (OSC) as an integrated industrial area over 1072.38 acres of land in Pen Taluka, District Raigad of Maharashtra. The land is spread over four land parcels located in close proximity adjacent to the NH 17 and SH 87 i.e Pen-Khopoli Road and close to River Bhogeshwari and River Balganga. The nearest railway station is Pen situated on the Panvel - Roha route of Central Railway. The Project will have Industrial (less polluting), Residential & Commercial clusters with state-of-the-art infrastructure and globally benchmarked smart features. The project development envisages Indian and foreign investments over a period of 15 years, creating a total built-up area of 93.09 million square feet of industrial, residential and commercial space. The project also aims to become home to a population of approximately three lakhs and create job opportunities for approximately 1.5 lakhs skilled and unskilled professionals.

2.0 **Project Opportunities**

The site falls within two planning areas namely Raigad Regional Plan boundary (approximately 900 acres) and Mumbai Metropolitan Region (MMR) Development Authority (- approximately 100 acres) limits. The project site spread across over 1072.38 acres of land, is closely clustered at four locations i.e. Site T1; T2; T3 & T4. The site parcels are located in close proximity to India's financial capital, Mumbai. The project boundary is linear irregular shaped clustered around four land parcels that fall within the Delhi Mumbai Industrial Corridor (DMIC) influence zone. The site cluster is well connected and is in close proximity of the Jawaharlal Nehru Port (JNPT), the well-developed urban center of Navi Mumbai, the proposed Mumbai Trans-Harbour Link (MTHL) and the proposed Navi Mumbai International Airport (NMIA). The Project topography is generally flat and with gentle gradient with moderate undulations with an average contour of about 200 mtrs. The Project is located at a travel distance of about 45 km from South Mumbai via proposed Mumbai Trans Harbour Link and 25 km distance from new proposed Navi Mumbai International Airport. The proposed Project is envisaged to become a 'City of Opportunity' that prides in providing 'Smart services for all, Employment for all & Accommodation' (SEA) for all. The Project is planned on the 3P principle – People, Planet and Profit; to effectively address the Social, Economic & Environmental concerns. The Project will comprise of residential area, industrial, and commercial land use and will also have basic provisions of city infrastructures viz; roads, amenities, bridges, water supply infrastructure, wastewater infrastructure etc.

3.0 Project Salient Features

The salient features of the project are given in Table-1.1

Sr.No	Particulars	Details /Values	
1	Name of the project	Orange Smart City	
2	Location	Pen, Raigad	
3	Total site area	1072.38 acres (4339767.89 sq.m)	
4	Total Built Up Area	8.64 million sq.m	
5	Category as per EIA Notification 2006	Industrial Estate $-7(c)$	
6.	Type of industries	Logistics, Engineering, Agro,	
		Electronics and Semi-Conductor, Life	
		Sciences, Information technology,	
		Gems and Jewellery, & Research and	
		Development and these industries are	
		less polluting.	
7	Industrial Built Up Area	1821828.61 sq.m	
8	Commercial Built Up area	2505594.98 sq.m	
9	Residential Area	4188998.07 sq. m.	
10	Green Area	267.87 Acres (1084031.43 sq.m)	
11	Amenities / Utilities	24154.79 sq.m	
12.	Estimated Population	3,00,000 nos	
13	Estimated Employment Opportunities	153923	
14.	Project cost Rs.	INR 2032 crores (+ INR 2000 Crores	
		land cost)	
15	Source of Power	Maharashtra State Electricity	
		Distribution Company Ltd.	
		(MSEDCL)	
16	Power requirement -		
	Construction Phase -	5 MVA	
	Operation Phase -	353 MVA	
17	Source of Water	Hetwane Dam	
18	Water requirement		
	Construction Phase	45 CMD	

Table-1.1: Project Salient Features

Sr.No	Particulars	Details /Values
	Operation Phase	62 MLD
19	Wastewater Generated	
	Construction Phase -	36 CMD
	Operation Phase -	46 MLD
20	Solid waste Generation :	
	Solid waste from residential areas	111 TPD
	Solid waste from industrial areas	10 TPD

4.0 Alternative Site Selection and Evaluation

The following three sites in Raigad District were considered and evaluated:

- a) Tarankhop Ramraj and Dhavate
- b) Meleghar and Kashmire
- c) Borgaon, Shene, Virani, Belavade, Walak, Mugoshi, Govirle & Hamrapur

The comparison of the three alternative sites considered on the various key parameters is presented below in Table-1.2 :

Sr.	Aspect	Site – 1	Site – 2	Site – 3
No		Tarankhop &	Meleghar &	Borgaon, Virani,
		Ramraj	Kashmire	Shene, Ambeghar,
				Belawade, Khurd,
				Belawade Budruk,
				Mungeshi, Govirle
1.	Connectivity	From state Highway	Access from ODR 28	Very good multi point
		and indirectly from	of Pen Tehsil	access on National
		National Highway	Required ROB on	Highway and State
			Railway for access	Highway.
			from NH-17	Also feasible to have
				railhead and water
				transport connect near
				Hamrapur.

Table-1.2: Comparative statement of alternative sites

Sr.	Aspect	Site – 1	Site – 2	Site – 3
No		Tarankhop &	Meleghar &	Borgaon, Virani,
		Ramraj	Kashmire	Shene, Ambeghar,
				Belawade, Khurd,
				Belawade Budruk,
				Mungeshi, Govirle
2.	Terrain	Plain	Plain	Plain land with gentle
				Slopes
3.	Availability	50% Irrigated and	80% Irrigated and	Barren Waste land
	of Land	50% Fallow Land.	20% Non-irrigated	suitable for industrial
		Hence more		development.
		agricultural land will		
		be used for the		
		project		
4.	Cost	High	Unaffordable	Relatively affordable
5.	Water	Water can be	Only Hetwane Dam	Water can be available
	Availability	available from	is nearest water	from Hetwane Dam
		Hetwane Dam	source	One more water source
				required for T4 & T3
6.	Manpower	Good	Moderate	Good
	Availability			
7.	Proximity to	Proximity to the	Proximity to the	Proximity to the
	JNPT	proposed MTHL &	proposed MTHL &	proposed MTHL &
		JNPT within 30 to 35	JNPT within 30 to 35	JNPT within 25 to 30
		km respectively	km respectively	Km respectively

Based on the comparative evaluation of the three identified sites, it was decided that the third location covering villages Borgaon, Virani, Shene, Ambeghar, Belawade, Khurd, Belawade Budruk, Mungeshi, Govirle was highly suitable for locating the OSC at the current location.

5.0 Proposed Land Use

The Project layout has been designed to keep the industrial, residential and commercial activity in relatively distinct zones though the industrial activity is less- polluting falling in 7 (C) category. As per the design layout the Project is in four predominant land use zones details of which are presented in Table-1.3

Table-1.3: Details of the land use-parcel wise

Sr.	Land	Physiography	Type of Proposed Use	Total	Affected	Percen
No	Use			site area	area in	tage
	Zone			(Acres)	acres	
1.	T 1	Gentle Slope	Predominantly	723.33	173	24%
			Industrial with low			
			Residential and			
			Commercial Land Use			
2.	T2	Plain open	Predominantly	102.63	-	-
		land	Industrial with low			
			Residential and			
			Commercial Land Use			
3.	Т3	Partially	Predominantly	113.23	16	14%
		impacted by	Residential and			
		CRZ -III	Commercial			
4.	T4	Plan open land	Predominantly	133.19	-	-
			Residential and			
			Commercial			
Tota	Total project area				189	18%

The project area is currently undeveloped or underdeveloped. All the four land parcels are vacant, dry barren without any vegetative growth or manmade structures. As per the proposed development, out of the total land use, nearly 57 percent planned for Industrial, Residential and Commercial purpose and 6 percent for Amenities / Utilities / Facilities, together which forms 63 percent of the total project area. Balance 37 percent is proposed for major roads and Undevelopable / Green / Open Space. Part of the T3 land parcel (approximately 38 acres out

of 113 acres in T3) comes under CRZ-III limit which will be used for activities permissible in CRZ-III areas.

The details of the land spread over four locations is shown in Table-1.4

Site	Name of Village	Area in Acres		
T1	Borgaon, Shene, Ambeghar and Virani	723.33		
T2	Belawade Budruk	102.63		
T3	Balawali, Govirle, Kopar, Ambiwali and Hamrapur	113.23		
T4	4 Mungoshi, Walak, Ambeghar, Belawade-Khurda, Padale and			
	Belawade Budruk			
Total A	1072.38			

 Table-1.4 : Details of the existing land

The area between the bridge on the Bhogeshwari river (100m from the project site) and the irrigation canal leading to Hetwane Dam (300 m from the project site) is proposed to be developed as a golf course which will compatible to the proposed land use. It is also to be noted that the proposed Balganga project is located at a distance of 1.82 km from the T4 land parcel.

The proposed land use distribution of the Project is shown in Table-1.5

 Table-1.5: Proposed Land Use Distribution

Land use	Area in Acres	Percentage
Industrial	390.00	36%
Commercial Area	88.43	8%
Residential Area	138.23	13%
Major Roads	128.86	12%
Undevelopable/Green/Open	267.87	25%
Amenities/Utilities / Facilities	58.99	6%
Total	1072.38	100

6.0 Description of the Environment

The baseline environmental status was studied for the following components:

- a) Meteorology
- b) Air Quality
- c) Noise Quality
- d) Water Quality
- e) Soil Quality
- f) Ecology and
- g) Socio-Economic component

The salient findings / interpretation of each of the components is given below:

A. Meteorology

An onsite meteorological station was installed to study wind speed, wind direction and temperature during the period from March 2016 to May 2016. The predominant wind direction during the period was from the West –North West quadrant. The findings are summarised in **Table-1.6**

Month	Wind speed ((m/sec)	Temperature (⁰ C)		
	Max	Min	Avg	Max	Min	Avg
March -2016	5.5	0	1.25	39.1	18	26.8
April-2016	6	0	1.6	36	20.9	27.7
May -2016	4.6	0	1.57	34	23.4	29.4

Table-1.6 : Synopsis of onsite meteorological data

The onsite meteorological data was compared with data from the nearest India Meteorological Department (IMD) station Murud. The predominant wind direction as per the IMD Murud station is from the West –North West quadrant. The summary of the IMD data is presented in Table-1.7

Table-1.7: Synopsis of the IMD Murud data (March 2014 to May 2014)

Month	Wind spe	ed		Temperature (0C)			
	(m/sec)						
	Max	Min	Avg	Max	Min	Avg	
March -2014	4.1	0	1.2	38.6	17.8	27	

Month	Wind speed		Temperature (0C)			
	(m/sec)					
	Max	Min	Avg	Max	Min	Avg
April-2014	3.9	0	1.4	36.6	19.2	27.7
May -2014	4.6	0	1.5	34.3	23.8	29.6

The onsite meteorological data is in general agreement with the IMD Murud data. The minor differences are observed due to the difference in the period of recording.

B. Ambient Air Quality

The ambient air quality was recorded at the 14 stations. The air quality was recorded w.r.t. the following parameters:

- i. Particulate Matter less than 10µm (PM10)
- ii. Particulate Matter less than 2.5µm (PM2.5)
- iii. Sulphur dioxide (SO2)
- iv. Oxides of nitrogen (NO2)
- v. Carbon monoxide (CO)
- vi. Hydrocarbon (HC)
- vii. Volatile Organic Compounds (VoC)

The maximum 24 hourly values of the PM_{10} , $PM_{2.5}$, SO_2 , NO_x were found to be within the National Ambient Air Quality Standards (NAAQS) limit. The CO levels were also found to be within the NAAQS limit of 2 mg/m³ for 8 hours. The Hydrocarbons and the VOCs were found to be below detectable limit throughout the monitoring period.

C. Noise Quality

The noise quality was recorded at 11 locations. The noise levels (Leq) observed during daytime in residential zone is in the range of 42.5 (Crosswind of T-3 at Kopar village) to 43.9 dB (A) (Upwind of T-1 Wirani Village) while during nighttime it is 32.5 (Downwind of T-4 at Mungoshi Village) to 33.8 dB (A) (Downwind of T-3 at Jite. village). The results reflect that the Leq (day) and Leq (night) was within the limits stipulated by Central Pollution Control Board (CPCB).

D. Water Quality

The ground water quality and the surface water quality was recorded at 6 stations and 8 surface monitoring locations. The ground water quality parameters were analysed are per IS 10500. The ground water results reflect that the calcium slightly exceeds the desirable limit of 75 mg/lit. The surface water quality parameters reflect that the water is chemically and bacteriologically non-potable at three locations while it is potable at remaining five locations.

E. Soil Quality

The soil quality was recorded at 8 locations. The results indicate that the texture was mostly clay and clay loam. The range of micronutrients reflect that the soil has good fertility level and fulfils the minimum nutrient requirement for growth of plants.

F. Ecology and Biodiversity

An elaborate ecology and biodiversity study was conducted within the impact zone (10-15 km radius) of the project site. The conclusions of the study are given below:

i. The project site does fall in the Western Ghats but is devoid of any Ecologically Sensitive Areas (ESA) as the entire project site is in "PEN" taluka and Pen taluka does not come under ESA as per the Report of the Western Ghats Ecology Panel under chairmanship of Prof Mahdav Gadgil, Report of the High Level Working Group on Western Ghats under chairmanship of Dr. K. Kasturiragan and the second draft notification no. S.O 2435(E) dated 4th September 2015 issued by the MoEF&CC. However there are some villages notified as ESA and are within the 15 km radius buffer zone of the project which are enlisted in the Table-1.8

r	Table-1.8: Villages in the 15 km radius of Orange Smart City notified as Ecological					
•	Sensit	ive Area				

Sr.	Taluka	Village	Distance from the project
no.			boundary (km)
1.	Sudhagarh	Tadgaon	8.6
		Uddhar	12
2.	Khalapur	Karambeli	10.97

		Talavali	11.54
3.	Roha	Palas	12.32
		Kondgaon	12.8

- i. The project site is outside any recorded forest areas. The landscape features include flatlands with a gentle gradient and scrublands in the region.
- ii. In the project site, no formal logging of wood and other such activities were observed, however the exploitation of the forest resources by nearby villagers and local communities was evident in the surroundings of the project site. The telltale marks of forests fire were also visible near two locations viz. Chirner and Palas village.

a) Flora

- i. By and large the habitat is prevalent with evergreen and deciduous foliage.
- ii. Amongst the locations surveyed, it was observed that many of the sites have localised biological diversity with variety of evergreen tree species as well as shrub layer.
- iii. The development activities may result in clearing of plant species mostly grasses and shrubs which are not unique or rare species because of their abundant occurrence in other areas. Thus, the loss of these species would have no serious ecological consequences.

b) Fauna

However, the project area could be home to general avifaunal species which are widespread and therefore any loss of habitat may not lead to any major loss in species numbers or diversity. Generally the concerns of non-recorded species do exists although it may be on a smaller scale owing to their non-sighting in the three-day sampling period between Dec 16-18, 2015.

c) Endangered Species

The study area does not have recorded presence of any critically threatened species. It was noted that many of the floral species found during the monsoon season especially grasses and herbs are not found in the majority of the dry season of the year.

G. Socio – Economic Profile of the study area

The socio-economic baseline environment is described with respect to the various parameters are as given below:

i. Demographic profile

According to the 2011 Census data, population in the total study area was 364915 living in 84345 households whereas the villages population in the project area was 11187 persons that is about 3% of the total study area population and the population of all the rural villages within the 15 km radius of the study area

ii. Social Groups

The proportion of Scheduled Castes (SCs) and Scheduled Tribes (STs) population within the project study area is on an average 3.0% and 15.3% respectively. The proportion of SC population in affected villages is merely 0.8% found only in 13 villages, which is less than other rural villages (2.2%) and urban centres (4.9%) in the study area. Whereas the proportions of ST population for villages within the project area is (43.9%), which together constitutes to 44.7% which is much higher than the other rural villages (21.9%) & urban areas (18.3%)

iii. Sex Ratio

According to 2011 census, sex ratio in the total study area was found to be 953 while in the affected villages was found to be 972. The sex ratio in the villages other than the affected villages was found to be 957.

It is important to note that, literacy rate for male and female in project affected villages is 57% and 43% respectively which indicates that the literate male population is more than the female literate population.

iv. Vulnerability

As regards vulnerability, poverty is actually a reason for making any section of a population vulnerable. The data for families below poverty line for the all the villages in study area is not available. However based on the studies in other areas of Maharashtra, most of the SC and ST families can be considered as the vulnerable

group which constitutes about 45% of the total population in the project affected villages in addition to any other BPL families in the region.

A primary baseline survey was also conducted by BEIPL and the details can be referred in the EIA study report.

v. Consultation with the villagers

The minutes of the consultation with the villagers in the affected area is given below in Table-1.9 below .

Table-1.9 : Will	able-1.9 : Windles of the consultation with the vinagers			
Date of Visit	20/10/2015			
Venue :	Project Site			
Client	BEIPL : Mr. Hrushikesh Kolatkar			
	Client : Representative from Client			

Village Name	Kopar village	Belawade village	Ambeghar village				
Discussion Poi	Discussion Points:						
Key points of	The village has school only for Primary	The village has a total of 328 houses	The village Ambeghar has 427 houses. The				
the meeting	level and for Middle and high school	The school in the village is only up	village has relatively large population. It can				
were	students have to go to Jambhul tep, Pen.	to eight class. For studies after eight,	be seen that the village is well connected by				
	There is no primary health center	students have to go to Pen.	road.				
	facility. For critical health related	There is a private clinic of a	The village has Government school up to 8th				
	matters, Pen is the nearest place.	Physician in the village. The nearest	standard. For studies after eight, students have				
	Rain water and Dug-well are the main	government primary health center is	to go to Pen.				
	sources of irrigation. For domestic use,	at Pen village.	There is a private doctor in the village. The				
	Dug-well and Hand pumps are the	Most of the village land is rain fed	nearest government primary health center is at				
	sources.	for agriculture purpose. For the	Pen.				
	Most of the people in the village are	domestic use well and hand pumps	Most of the village land is irrigated through				
	engaged in agriculture, dairy. Rice and	are the sources.	dug-wells and tube wells.				
	seasonal vegetables are cultivated by						

Table-1.9 : Minutes of the consultation with the villagers

the people. Most of the seasonal	People of the village in general are	For domestic use, dug-wells and hand pumps
vegetables grown are sold in Pen and	engaged in agriculture, dairy and	are the sources of water for villagers.
Navi Mumbai. Almost each family has	daily wage labourers. Rice and	People of the village in general are engaged in
cows or buffaloes to supplement their	seasonal vegetables are cultivated	agriculture, dairy and wage labour. Main
income by selling milk. There are also	by the people. Seasonal vegetable	crops is rice and seasonal vegetables are also
people who are engaged as daily wage	grown are sold in nearby urban	cultivated. Some families are fully into
labourers in agriculture and	areas.	vegetable cultivation which is a main source
construction activity in nearby urban	Almost each family has cows or	of income.
areas.	buffaloes to supplement their	In addition to agriculture, the other two main
Women in general support the family by	income.	occupation for earning for the locals is dairy
engaging in agriculture and dairy	About half the male population of	and wage labour. Almost each family has
activity & household chores.	village is engaged in construction	cows or buffaloes to supplement their income.
	activity in nearby urban areas.	Most of the male population of villages is
	The education level is generally low	engaged in construction and factories in Pen
	among the villagers	as wage labor.
	Women in general support the	The education level is generally low among
	family with household chores. In	the villagers.
	addition, women are also involved	Women in general support the family with
	in agriculture and dairy activity of	household chores. In addition, women are also
	family.	involved in agriculture and dairy activity of
		family.

Key	People are aware about the project and	People are aware about the project	People are aware about the project and have a
observations	have a very positive opinion on the	and have a very positive opinion on	very positive opinion on the project.
and issues:	project.	the project.	People expect the project would bring
	People expect the project would bring	People expect the project would	development in their villages and would open
	development in their villages and would	bring development in their villages	up opportunity of employment and other
	open up opportunity of employment and	and would open up opportunity of	business avenues
	other business avenues	employment and other business	People were keen to know when the project
	People were keen to know when the	avenues	would start and what kind of factories will
	project would start and what kind of	People were keen to know when the	come up
	factories will come up.	project would start and what kind of	People also expect the project to give
	People also expect the project to give	factories will come up	preference to local in employment
	preference to local in employment	People also expect the project to	In project construction phase the locals can be
	Unemployment and lack of opportunity	give preference to local in	good source of construction labour as they are
	is evident in the village.	employment	already in to that activities currently.
		In project during the construction	There is large scale unemployment reported
		phase the locals can be good source	during the survey
		of construction labour as they are	
		already in to that activities currently.	

7.0 Anticipated Environmental Impacts and Mitigation Measures

The anticipated environmental impacts and mitigation measures during construction phase along with responsibility of implementation and cost are tabulated below:

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
1.	Ambient Air	Emissions from	Suppression of fugitive dust emissions by spraying water,	Implementation	Engagement of
	Quality	construction	wetting of the stockpile,	by Contractor and	sprinklers:
		equipment, vehicles	Proper maintenance of machines and vehicles.	Supervision by	3,00,000 per
		Improper handling	Contractors to maintain proper records for fleet engaged.	OSCIPL	sprinkler unit
		and storage of	Dust control equipment such as bag house, or cyclone to		
		construction	be employed.		
		material	Limited vehicular movement to be permitted on disturbed		
		Fugitive dust	soil.		
		emissions	Minimum possible drop height to be maintained while		
		Emissions from	unloading /screening of material.		
		onsite operation of	Stockpiling of excess fill material.		
		diesel generators	Paved roads to be cleaned regularly and un-pave roads to		
		Burning of waste at	be stabilized and watered regularly.		
		camp sites	Vehicle speed to be restricted to 25 km/h on unpaved		
			roads.		
			Covers and enclosures to be provided for loose		
			construction material at construction site.		

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
			Trucks /dumpers engaged to be covered during off site		
			transportation.		
			A minimum freeboard of six inches to be maintained by		
			haul trucks when material is transported on any paved		
			road.		
			Vehicles with valid Pollution under Control (PUC)		
			certificate to be engaged for project.		
			Upwind fencing to be projects.		
			Soil binders to be used for stabilizing sloping surfaces.		
			Downwash of trucks to be undertaken prior to departure.		
			Inactive disturbed surfaces to be sprinkled with water on		
			daily basis.		
			Power supply for construction will be sourced from local		
			distribution company.		
			Generators to be used only as backup source.		
			Diesel generators to be optimally operated and regularly		
			maintained.		
			Appropriate stack height as per the CPCB guidelines to be		
			provided for DG sets.		

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
			LPG cylinders to be provided in labour canteens and use		
			of fuel wood to be discouraged.		
			Open burning of waste shall not be permitted.		
			Community kitchen to be promoted among sub -		
			contractors		

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
2.	Water	Change in	Water for construction phase to be sourced from existing	OSCIPL	10,000 per
	Resources	topography and	sources allocated to PP supplemented with authorized		toilet with
	and Quality	alteration of	tanker supply.		septic tank and
		drainage pattern	Optimal water conservation measures at camp sites along		soak pit
		Sediment run off	with adequate awareness programmers to be organized for		arrangements
		from construction	the workers.		
		area	Adequate number of toilets (at least 8-10 toilets per 100		Storm water
		Disposal of sewage	labours) with septic tanks and soak pits arrangements to be		drains with silt
		from labour	provided onsite.		traps and
		facilities	Random disposal of wastewater from labour colonies to be		collection
		Contamination of	restricted.		sump: 5-7
		surface and	Adequate drains and collection sumps to be provided		lakhs per
		groundwater	around labour facilities.		labour facilities
		resources due to oil	Sludge from waste water treatment systems to be disposed		
		and grease /sewage	off properly.		Rain water
			Regular removal of debris from construction site to be		harvesting
			practiced.		structure for
			Secondary containment and bund shall be provided around		construction
			excavated soil or loose construction material.		labour facilities
			Storage area to be kept away from the storm water drain.		: 40,000 per

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
			Oil and grease containing effluents to be pre-treated before		recharge pit/
			discharge.		storage unit
			Silt traps and bunds to be set-up around construction sites.		
			Adequate slopes and drainage channels to be provided		
			across the project site, without disturbing any natural		
			drainage.		
			Rainwater harvesting opportunities to be explored and		
			implemented.		

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
3.	Landscape	Change in existing	The 90% soil requirement will be fulfilled from cutting	OSCIPL	Greenbelt
	and	land use from	within the site and only 10% will be sourced from		buffers :
	Topography	agricultural to	approved quarries.		2,00,000-
		mixed use	Excavated soil to be used in level raising;		5,00,000
		(including	The construction contractors shall be instructed not to cut		Depending on
		industrial and	any tree.		area to be
		residential)	Green area and green buffers will be developed to improve		covered.
		Change in	the landscape.		
		topography	Diversion dykes to channel runoff to be constructed around		
		Change in drainage	the excavated site.		
		pattern	Land surface contours to be restored in relation to the		
		Localized flooding	surroundings.		
		and related health	Construction footprint will be well defined and		
		issues due to	construction work to be carried out within the Project		
		decreased	footprints only.		
		infiltration	Road corridor to be provided with adequate cross drainage.		
4.	Soil	Soil Erosion and	Top soil to be preserved and reused for landscaping	OSCIPL	Cost of erosion
	Resources	compaction	purposes		prevention
		Soil contamination			measures to be

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
			Clearance of vegetative cover to be minimized to the extent		identified after
			possible and redeveloped latter on.		detailed survey
			Site grading and excavation to be undertaken during dry		
			season.		
			Dikes, berms, drainage swales or ditches to be provided to		
			divert surface run-off.		
			A retention wall or bund to be provided around the storage		
			areas for excavated soil and other construction material.		
			Completed earthworks to be sealed and/or re-vegetated at		
			the earliest with the help of landscape expert.		
			Stacking of excavated soil material will be made only in		
			earmarked areas.		
			Excavated soil to be used/ transported at the earliest for		
			filling low lying areas.		
			Proper routing and adequate capacity of the storm water		
			run-offs drains to be provided.		
			Movement and parking of heavy machinery and vehicles		
			to be restricted to identified area.		
			Area used for parking purposes to be restored immediately		
			after completion of each project activity.		

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
			All storage facilities to be designed with paved surface,		
			provided with covered shed and adequate containment		
			facility at the construction.		
			All waste to be handled as per applicable regulations.		
			Hazardous waste to be handled and disposed off in		
			accordance with the requirements of hazardous waste		
			management rules 2008 and Hazardous and Other Wastes		
			(Management and Transboundary Movement) Rules,		
			<mark>2016</mark> .		
			Portable oil spill containment and clean-up equipment to		
			be made available at construction site and training for use		
			of such equipment to be imparted.		
			Provision of covered bins at labour facilities		
			Waste to be segregated in biodegradable and non-		
			biodegradable components.		
			Biodegradable waste to be used for animal feed/ vermi-		
			compost/ manure.		
			Contaminated sand/ soil shall be prevented during		
			construction activities.		

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
			Trainings to be imparted to all workers and subcontractors		
			regarding hazardous waste storage and disposal		
			procedures.		
			On completion of construction activities, septic tanks for		
			camp sites to be abandoned and filled with earth.		
5.	Traffic and	Increased traffic	Wherever required temporary widening of roads to be	OSCIPL	Cost of road
	transport	volume	undertaken.		improvement
		Additional traffic	Traffic and heavy machinery movement schedule to be		to be estimated
		load on existing	communicated clearly to the local inhabitants. Prior		after detailed
		village roads	consultation with local Police and local Panchayat to be		survey
		Disruption of traffic	undertaken.		
		and increased cases	Providing dedicated path within the site for entry and exit		
		of road related	of the construction vehicles		
		hazards	Roads damaged due to project vehicles will be		
			continuously repaired.		
			Provision of adequate training to drivers.		
			Dedicated parking area to be provided for project vehicles.		
			Parking along footpaths, single lane roads shall be		
			prohibited.		

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
			Detailed plan for signage around the construction areas to be prepared to facilitate traffic movement. Inventory of the vehicles used in project and construction equipment along with their PUC's to be maintained.		
6.	Ambient Noise Quality	NoiseduetoConstructionactivitiesactivities(such asexcavation,grading,erectingequipment,piling,etc)Noiseduetooperationoperationoperationandmachinery	Adequate planning to avoid high noise activities to be undertaken. Acoustic enclosures, noise barriers to be provided in areas of high noise generating sources. Rubber padding to be provided for vibration control Movement of vehicles during night time to be limited. Construction workers to use ear muffs in areas with potential for high noise generation. Regular maintenance of vehicles and repair of equipment. Noise barriers will be provided between the activities and the receptors.	OSCIPL	PPE for noise: 20,000- 30,000 per month

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
		Movement of vehicles Noise due to construction equipment such as Concrete Mixers (2Nos) and	Restriction on use of equipment generating high noise during night time. Working hours and construction activities to be aligned and works to be prohibited during night hours.	Contractor	
		Batching Plant	• Acoustical enclosures are strongly recommended with 30 dB Transmission Loss Rating for the Engine, to bring	Contractor	4,00,000/- 2,00,000/-
			down the SPL below 80 dB.		

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
			The contractor should carefully choose the batching plant		
			in order to meet with the CPCB Norms.		
			• Hydraulic pumps and compressors should be covered with		
			Acoustical Enclosures with 20 dB Transmission Loss		
			Rating in order to reduce the noise.		
			• Valves should be covered with Removable Acoustical		
			Blankets.		
			• The contractor should choose controlled operating hours		
			for noisy activities such as delivery, loading unloading etc.		
7.	Socio-		Affected land losers to be considered for benefits like	OSCIPL	
	Economic	Loss of existing	employment, contracts etc.		
		village assets	Skilled and qualified entitled persons to be given		
		Loss of	preference in employment and other contractual benefits.		
		landholdings	Procurement of community land to be avoided to the extent		
		Impact on	possible and adequate buffer area to be retained around		
		livelihood of the	villages.		
		villages			
		Loss of livelihood			

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
		Loss of Common			
		Property Resources			
8.	Labour	Location of labour	Optimal water conservation measures at camp sites along	OSCIPL	
	Camp	facilities.	with adequate awareness programmers to be organized for		
	Management	Domestic solid	the workers.		
		waste generation	Adequate number of toilets (at least 8-10 toilets per 100		
		Firewood for	labors) with septic tanks and soak pits arrangements to be		
		cooking and	provided onsite.		
		burning of garbage	Random disposal of wastewater from labour colonies to be		
		Indoor air quality	restricted.		
		issues	Adequate drains and collection sumps to be provided		
		Waste water	around labour facilities.		
		generation	Regular removal of debris from construction site to be		
		Health and hygiene	practiced.		
		issue	Integrated solid waste management plan will be developed		
			for collection, transportation, treatment and disposal of		
			waste.		
			Workers to be provided with health and safety training.		
			Safety measures, including use of temporary fall protection		
			and out edges of elevated work surfaces, such as hand rails		

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
			and toe boards to prevent materials from being dislodged		
			shall be done for workers while working at heights.		
			First aid and essential medical services to be provided at		
			site.		
9	Occupational	Injury due to	Manual transfer of heavy loads to be minimized by proper	OSCIPL	Training for
	Health and	improper handling,	work site layout.		workers :
	Safety	operation and	Good housekeeping practices to be exercised.		6,00,000/- year
		execution	Measures such as job rotations and stretch breaks to be		PPE for
		Trip and fall,	adopted.		construction
		inadequate fall safe	Proper signage to be provided around construction site.		25,00,000/-
		arrangements	Use of Personal Protection Equipment (PPEs) to be		year
		Exposure to	mandated at work site.		approximately
		hazardous	Workers to be provided with health and safety training.		
		substances	Use of temporary fall protection measures in scaffolds and		
			out edges of elevated work surfaces, such as hand rails and		
			toe boards to prevent materials from being dislodged shall		
			be done.		
			Safety harness to be ensured for workers while working at		
			heights.		

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
			First aid and essential medical services to be provided at		
			site		
10	Employment	Increased	Project to utilize the facilities available from the local	OSCIPL	Adequate cost
	and Local	employment	market to support the local economy to the extent possible.		will be
	Economy	opportunities	Wherever possible, labour from local community will be		allocated from
		Contracting	employed for project.		the project cost
		opportunities for			for skill
		locals			development of
	Better avenues for				local youth
		Small scale service			through
		providers			training
					programs

Sr.	Component	Impacts Identified	Suggested Mitigation Measures	Responsibility	Estimated
No.					Cost (INR)
11	Ecology	Loss of trees and	Original soil profile shall be retained by storing each	OSCIPL	Awareness and
		ground vegetation	excavated layers separately and restoring it later.		training of
		Habitat destruction	Tree felling to be minimized to the extent possible.		workers:
		Adverse impact on	Contractors shall be instructed to practice the same.		10,00,000
		wildlife due to	Hunting activities will not be permitted within and around		
		noise, vehicle	the delineated area.		
		movement,	Raw materials and debris to be stored away from water		
		poaching,	bodies, streams and run off areas.		
		illumination	Standard noise levels to be maintained during construction		
		Increased turbidity	activities.		
		and siltation	A 'Local Ecological Monitoring Group' will be setup to		
			monitor the environmental and ecological safeguard		
			measures during construction phase.		
			Audio visual hall for training at the time of registration of		
			new labourers on site.		

8.0 Anticipated Environmental Impact & Mitigation Measures

The anticipated environmental impacts and mitigation measures along with responsibility of implementation and cost during operation phase are tabulated below:

Sr.	Compone	Impacts	Suggested Mitigation Measures	Responsibility	Estimated
No.	nt	Identified			Cost (INR)
1.	Ambient	Emission	Power demand has been estimated as a part of master plan and dedicated	OSCIPL	Buffers areas
	Air	from power	power supply system has been planned for OSC		are
	Quality	backup/ DG	DG sets to be located in the downwind direction with respect to residential		incorporated
		sets	areas.		in the project
		Stack	OSCIPL developed for overview of power supply shall ensure that the		cost
		emission	power failure is maintained at minimal.		Cost of
		from	Stack heights for DG sets to be maintained as per CPCB/MoEF&CC		Pollution
		industries	norms.		Control
		Fugitive	Comprehensive planning has been undertaken as a part of master plan		Equipment
		emission	development to mitigate impacts due to industries.		will be borne
		from	Planning ensures that the proposed Industrial areas and existing residential		by the
		industrial	lie in the upwind or cross wind direction.		individual
		processes	Residential areas have been separated from industries by the provision of		Project
		Emissions	suitable buffers.		entities
		from increase			

Sr.	Compone	Impacts	Suggested Mitigation Measures	Responsibility	Estimated
No.	nt	Identified			Cost (INR)
		in traffic	Individual industries will be required to obtain adequate approvals such as		
		volume	Consent to Establish / Consent to Operate or environment clearance from		
			MPCB / SEIAA / MoEF&CC.		
			All emission sources to be provided with adequate stack height as per		
			CPCB / MoEF&CC norms.		
			Low emission fuels to be used by industries.		
			Air pollution control equipment to be employed by industries.		
			Good housekeeping to be practiced.		
			PP to organize seminars and Capacity Building training programmes		
			about the best practices in different industrial sectors.		
			PP in association with the MPCB to regularly monitor the environmental		
			performance of the industries.		
2	Ambient	Increase in	All habitations to have a suitable buffer area delineated around them.	OSCIPL	The cost to be
	Noise	noise levels	Vegetative barriers in form of green belt to be provided around all		estimated
	Quality	in residential	industrial areas.		based on
		areas and	All industrial operations to have acoustic enclosure and employ noise		industry type.
		adjoining	attenuation measures.		
		villages	All roads and highways to be provided with vegetative barriers and barrier		
		Impact on	walls.		
		avifaunal			

Sr.	Compone	Impacts	Suggested Mitigation Measures	Responsibility	Estimated
No.	nt	Identified			Cost (INR)
		species due	Diesel Generator Sets are supposed to have Sound Pressure Levels of		
		to increased	lesser than 75 dBA when measured at 1 meter distance. However, when		
		noise	multiple DG sets are supposed to be kept close to one another, a single		4,00,000/-
		Movement of	Acoustical Enclosure combined for all the DG Sets is recommended with		
		vehicles	a minimum Transmission Loss Rating of 30 dBA.		
		D.G sets			
		Sewage	STP consists of multiple of blowers and pumps, out of which blowers can		
		Treatment	generate noise levels exceeding 100 dB. Acosutical Enclosures for STP		20,000/-
		Plant	Blowers are strongly recommended, with 30 dB Transmission Loss		
			Rating.		
		Exposure to	All people working in the vicinity of the Equipment/Machinery with		
		high noise	Sound Pressure Levels higher than 90 dB should wear protective ear plugs		
		prone areas	to avoid permanent hearing damage.		
			Other mitigation measures		
			Sound Reflective barriers to be installed at the boundary of the project site.		10,00,000/- to
			If re-usable barriers aleady then the cost is nil. Otherwise it is as given in		20,00,000/-
			the column "Estimated Cost"		

Sr.	Compone	Impacts	Suggested Mitigation Measures	Responsibility	Estimated
No.	nt	Identified			Cost (INR)
3.	Water	Increase load	Individual projects will have separate water meters and two inlet sources	OSCIPL	Is
	Resources	on fresh	for use of treated wastewater;		incorporated
	and	water sources	Building and plumbing code to propose dual plumbing layout;		in Project
	Quality	Unplanned	SCADA system to be implemented for monitoring leakages in the water		Cost
		disposal of	conveyance system;		
		industrial	Providing training and education to the public on water conservation		
		waste water	habits and the value of drinking water;		
		generated	OSCIPL to organize information forums with industry/commercial		
		and sewage	owners;		
		Inadequate	To develop a risk management strategy to ensure water safety for the		
		management	project affected areas;		
		of storm	Monitoring of Unaccounted Flow of Water and detection of leakage shall		
		water	be done;		
		Spills, leaks	Improvement of management of water supply for integrated water supply		
		from	management system (IWSMS) using an information technology		
		industries,	application;		
		storage areas	A reliable technical department to be formed for maintenance and quality		
		Contaminati	control shall be established;		
		on of natural	Domestic and industrial wastewater generated will be treated separately;		

Sr.	Compone	Impacts	Suggested Mitigation Measures	Responsibility	Estimated
No.	nt	Identified			Cost (INR)
		water	An RWH Monitoring Cell to be formed which will be responsible for		32,40,850/-
		resources and	monitoring safe recharge and extraction of ground water in OSCIPL.		
		ground water	Areas for ground water recharge shall be identified and delineated; Rain		17,89,350/-
		aquifers	water harvesting tanks are proposed to conserve water		
			Recharge pits are planned for ground water recharge		
			Roof Top RWH shall be made mandatory for all residential, commercial		
			and industrial buildings and shall be monitored by the Cell periodically.		
4.	Solid	Inadequate	• Industries generating hazardous waste to comply with the	OSCIPL	Included in
	Waste	collection	requirements of Hazardous Wastes (Management and Handling)		project plan
	Disposal	and treatment	Rules, 1998 and Hazardous and Other Wastes (Management and		
		of domestic	Transboundary Movement) Rules, 2016.		
		waste	• OSCIPL for SWM to undertake benchmarking as per Ministry of		
		Unhygienic	Urban Development.		
		conditions,	• Integrated solid waste management plan will be developed for		
		odour	collection, transportation, treatment and disposal of waste.		
		problem	• Facilities will be designed to cater to the requirements of horizon		
		Localized	year		
		flooding	• Industries to contact hazardous waste management facility near		
			Taloja for disposal of their hazardous waste.		

Sr.	Compone	Impacts	Suggested Mitigation Measures	Responsibility	Estimated
No.	nt	Identified			Cost (INR)
		Contaminati on of soil and	 Biomedical waste to be managed in accordance with Bio-Medical Waste (Management and Handling) Rules, 1998 and Bio-Medical 		
		groundwater	Waste Management Rules, 2016.		
		Improper	• E waste to be sold to authorized recyclers. E waste to be managed		
		disposal of	in accordance with E-Waste Management Rules, 2016.		
		sludge and industrial waste	• Recyclable waste to be collected separately and sold to authorized recyclers/ vendors.		
5	Traffic	Increase in	The roads in general to be designed to carry the maximum traffic loads	OSCIPL with	Incorporated
	Volume	traffic flow	with anticipated future development and on a par with IRC (Indian Road	RTO	in the project
		Increase in	Congress) Standards;		cost
		private traffic	A well planned public transport infrastructure has been envisaged for the		
		volume	project;		
		Traffic	The proposed road circulation shall provide for safe and efficient		
		congestion	movement of people;		
		Irregular	Maintenance of systematic spatial and technical database for the roads		
		Parking	which would enable regular monitoring and feedback on road conditions		
			thereby managing effective periodic maintenance;		
			Pedestrian Guard Rails, Road safety Signage and overhead signs shall be		
			placed wherever necessary;		

Sr.	Compone	Impacts	Suggested Mitigation Measures	Responsibility	Estimated
No.	nt	Identified			Cost (INR)
			Road widths and lane configurations to be designed based on the modeling		
			exercise;		
			High occupancy vehicle (HOV) lanes shall be encouraged by differential		
			toll policy;		
			Non-motorized vehicles are encouraged		
			Comprehensive traffic and travel surveys shall be conducted every 5 years		
			to monitor traffic characteristics and travel behavior to develop strategies		
			for effective transportation;		
			Each individual project shall develop parking facilities as per the		
			Development Control Regulations.		
			Each residential project to provide parking facilities as per applicable		
			norms and regulations.		
			Sufficient Loading/unloading space to be provided.		
6.	Land use	Impacts on	During the master planning stage, detailed analysis has been undertaken	OSCIPL	Incorporated
	Pattern	existing	to delineate site for Orange Smart City and various site alternatives were		in the project
		human	examined and ranked to select the option based on socio-economic factors.		cost
		settlements	Adequate buffer has been provided around environmentally sensitive		
			features		
			Industrial land use has not been proposed in proximity of the sensitive		
			receptors.		

Sr.	Compone	Impacts	Suggested Mitigation Measures	Responsibility	Estimated
No.	nt	Identified			Cost (INR)
			All irrigation channels and surface bodies within delineated project area		
			are to be retained.		
			Fiscal measures to be undertaken to restrict unplanned development along		
			the peripheral areas.		
			To limit the development in the existing settlements, the Urban Planning		
			Department is to define the land use for these regions through the Master		
			Plan and limit the densities in these regions through the application of the		
			local applicable building bye laws.		
7.	Ecology	Impact on	As per master plan, no forest land is falling in the delineated area;	OSCIPL	Included in
		flora and	Only native and local species will be chosen for green belt.		the project
		fauna of the	Each industry shall develop green belt in 33% of the total land area as per		cost
		adjoining	the CPCB guidelines;		
		green areas	Development around the project area will be regulated and no		
		Illegal	unauthorized development will be allowed.		
		cutting of	All migrant workers and local contractors will be provided with fuel		
		trees.	arrangements at construction labour facilities		
		Bird kill	to avoid any discrete collection of fuel wood.		
		-Habitat	Transmission lines and chimneys will be provided with optical markers to		
		fragmentatio	enhance visibility for birds.		
		n and loss			

Sr.	Compone	Impacts	Suggested Mitigation Measures	Responsibility	Estimated
No.	nt	Identified			Cost (INR)
			No activities shall be planned in the green buffer other than approach/		
			service road, social forestry and horticulture, public amenities (activities		
			which would not result in damaging the green cover).		
			The fronts of river, drain, canal and Nallas, etc. passing through the town		
			are planned as green areas.		
8.	Socio-	Increased	OSCIPL and individual project to undertake CSR program to ensure	OSCIPL	CSR program
	Economic	employment	communal harmony and cooperation.		to be at least
		and business	The project to put in place OSCIPL responsible for efficient management		0.4% of the
		opportunities	and maintenance of infrastructure.		project cost
		Improvement	Orange Smart city is willing to spend CSR money in providing skill		for each
		in	development, clean and safe drinking water, sanitation facility, primary		Phase.
		infrastructure	health care support in the nearby villages.		Individual
		Increased			projects will
		income			further
		levels			enhance the
		Stabilization			CSR budget
		of the rural			based on their
		economies			project cost.

Sr.	Compone	Impacts	Suggested Mitigation Measures	Responsibility	Estimated
No.	nt	Identified			Cost (INR)
		Potential for			
		cultural			
		conflict			
		Unplanned			
		secondary			
		development			
		in the			
		adjoining			
		areas			

9.0 Environmental Monitoring Plan

The environmental monitoring plan for the proposed project has been developed in view of the institutional, scientific and fiscal issues pertaining to the project. For developing the monitoring plan, appropriate Value Ecosystem Components (VEC's) which are likely to be affected have been identified. For each component, suitable measurable environmental indicators which are appropriate to the impact mechanism and scale of disturbance and have a low natural variability, broad applicability and an existing data series have been defined.

A comprehensive environmental monitoring plan has been developed for the construction and operation phases of the Integrated Industrial Township. Monthly review meetings shall be carried out by OSCIPL to check for unplanned growth in protected areas. Water resources availability shall be regularly monitored by OSCIPL. OSCIPL shall also work in association with the Pollution Control Board (PCB) to monitor environmental compliance of individual projects and environmental quality of the region.

10.0 Additional Studies

An elaborate risk assessment study was carried out with recourse to various hazards (toxic, flammable, natural) including the hazard identification, MSDS, Fire and Explosion Index, HAZOP study, Consequence Analysis, Failure Frequency Analysis, Impact Assessment, Risk Estimation (Individual risk, Societal risk and F-N curve)' All the studies and analysis hence concluded that given the data and parameters, no major risks and hazards are predicted and risk mitigation measures have been suggested to reduce the risks to As Low as reasonably practical (ALARP). Also an Onsite DMP and an Offsite DMP has been delineated to counter the risks and the disasters.

11.0 Project Benefits

The Project is a planned mixed investment destination, with the objective of achieving high economic growth for the region with massive employment generation. The project will host electronics manufacturing industries, IT, residential sectors etc., supported by modern infrastructure, premium civic amenities, centres of excellence and proactive policy framework. The various direct and indirect benefits that will accrue from the project are listed below.

- a) Industrial Investment;
- b) Employment Generation;
- c) Capable to cater Domestic Market;
- d) Public investment in core infrastructure ;
- e) Benefits of Greenfield Development and High Access Corridor ;
- f) World-class infrastructure & connectivity;
- g) Housing to about 3,00,000 which will also include Social Housing

12.0 Conclusion

The EIA for Orange Smart City relies on primary and secondary sources of data including site visits and establishment of monitoring stations w.r.t air ,water noise, soil and ecology and biodiversity components. The project will benefit in generating employment and economic benefits to the Mumbai Metropolitan Region and its surroundings and will address Industrial demand and new emerging housing need including affordable housing.. Basis the studies, surveys and analysis it appears that the project may not have any adverse impacts on the environment and shall promote sustainable development.