



Notice

To,

Sub. :- Request for Proposal (RFP) for Electrical Work at Sub – Regional Office, Pune - 2

.....

Maharashtra Pollution Control Board invites sealed quotations for Electrical Work at Sub - Regional Office, Pune-2 located at 1st Floor, opposite Mahendra & Mahendra gate no. 1 & 2, Capital Square, Nighoje, Chakan MIDC, Phase 4, Pune – 410501. The detailed specifications of the work is mentioned in the below annexure. If require you may visit the site by prior appointment on any working day for assessment of the work and submit your quotation to the Executive Engineer, MPCB, 4th Floor Kalpataru Point, Opp. MovieMax Cinema, Near Sion Circle, Sion (E), 400 022 on this address within 7 (Seven) working days from the date of this letter.

The Member Secretary, Maharashtra Pollution Control Board reserves all right to reject any or all quotations without assigning any reason.

Annexure

Sr. No.	Description of Item	Qty	Rate	Amount
1	Supplying and erecting HMS PVC conduit FRLS grade 25 mm dia. with necessary accessories in wall/floor with chiselling appropriately	150	M	
2	Supplying and erecting mains with 3x2.5 sq.mm FR copper PVC insulated cable laid in provided conduit/trunking/inside pole/Bus bars or any other places.	300	M	
3	Supplying and erecting mains with 2x4 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places.	65	M	
4	Supplying and erecting ISI mark modular type switch 6A / 10A duly erected on provided plate and box with wiring connections complete.	12	Nos	
5	Supplying and erecting ISI mark modular type switch 16A duly erected on provided plate and box with wiring connections complete.	05	Nos	
6	Supplying and erecting ISI mark modular type 3 pin 6A multi sockets with safety shutter, duly erected on provided plate and box with wiring connections complete.	30	Nos	

7	Supplying and erecting modular type 3 pin 6 / 16A multi socket with safety shutter ISI mark approved make duly erected on provided plate and box with wiring connections complete.	10	Nos	
8	Supplying and erecting ISI mark modular type (two module) electronic step regulator for fan, duly erected on provided plate and box with wiring connections complete.	10	Nos	
9	Supplying and erecting ISI mark modular type blanking plate one module, duly erected on provided plate & box.	10	Nos	
10	Supplying and fixing Surface type 8 modular switch box with double mounting plate.	34	Nos	
11	Secondary point wiring for additional light/ bell point, Surface type in min 20 mm FRLS grade PVC conduit with 1.5 sq.mm. (2+1E) FRLSH grade copper wires with required accessories as per specification No: WG-PW/CW	40	Nos	
12	Supplying & erecting triple pole and neutral distribution board (SPNDB), SPMCB of 12 ways/phase, with door, 1.2mm thickness, surface/flush mounted, IP 43 protection on iron/GI frame (horizontal busbar type)	01	Nos	
13	Supplying, erecting & marking FP MCB 40A to 63A, with rated short - circuitbreaking capacity (Icn) 10kA in provided distribution board as per specification no.SW-MCB	01	Nos	
14	Supplying, erecting & marking SPMCB 6A to 32A, C-series with rated short circuit breaking capacity (Icn) 10kA in provided distribution board as per specification no. SW-SWR/MCB	10	Nos	
15	Supplying and erecting LED tube Light Max. 32 W	35	Nos	
16	Supplying and erecting LED square 2x2 Max. 18W down lighter/Panel	10	Nos	
17	Supplying and erecting energy saving ceiling fan 230 V A.C. 50 cycles 1200 mm complete erected in position as per specification no. FG-FN/CF	12	Nos	
18	Supplying and erecting fan hook box of 10 mm M.S. round bar bounded to the R.C.C. bars upto 50 mm length each side and pierced through a 16 S.W.G. thick aluminium/M.S. Bowl 100 mm dia. or equivalent square size and having depth upto 75 mm complete erected with duly painted by one coat of red oxide paint and two coats of paint erected in position and without any leakage of slurry of cement concrete on either side of the box and positioned to the bottom level of the slab.	12	Nos	
19	Supplying, erecting & commissioning 4 pole RCCB 40A, electromagnetic type with 30/100/300 mA sensitivity with earth leakage trip indication complete as per specification no. SW-RCCB/RCCB	01	No	
20	Supplying, installing, testing & commissioning split type variable speed inverter technology with minimum 3 to 1 convertible mode for compressor, room air conditioning unit 1.5TR capacity having ISEER minimum 3.8 to maximum 4.39 suitable to operate on 250V, 50 Hz, A.C. supply having 1 no of air handling unit hi-wall/floor mounting type complete with refrigerant R32 having copper condenser, minimum 2.5PM filter, self diagnosis feature, stabilizer free operation & temperature display on indoor unit, noise level maximum 50dBA at position as per specification no. APAC/ WAC	01	No	

21	Copper piping with insulation	20	Rft	
22	Electrical Cabel	23	Rft	
23	M S Out door Stand	01	No	
24	Supplying and erecting modular type telephone socket one gang with safety shutter, duly erected on provided plate and box with wiring connections complete.	15	Nos	
25	Supplying and erecting modular type computer Jack RJ45 with safety shutter,duly erected on provided plate and box with wiring connections complete.	15	Nos	
26	Supplying & erecting 2 pair telephone copper cable 0.5 mm dia. with high density polyethylene insulation, polyester taped, Nylon Rip Cord & grey colour sheathed with FR PVC, conforming to ITD specification S/WS 113C laid inprovided PVC casing capping/conduit as per specification No. WG-TW	250	Mtr	
27	Supplying and installing cat-6 LSZH cable suitable for networking as per specification no. WG-COC/NC	350	Mtr	
28	Supplying & erecting seamless outside & inside, smooth, dry and clean copper pipe with ROHS compliant suitable for refrigerant having 22SWG thickness and inner dia/size 16mm complete.	30	M	
29	Supplying, installing, testing and commissioning FRLS, XLPE armoured cable 2 core 1.5 sq.mm. copper conductor complete erected on wall/ ceiling complete as per specification no. CB-LT/CU (Note increase rate by 2% for FRLS)	130	M	
30	Providing and fixing of 3D Acrylic LED Glow Sign Board, comprising a primary structural framework of MS (Mild Steel) hollow square pipes treated with anti-rust primer. The fascia is to be clad with 3mm thick, exterior-grade Aluminium Composite Panel (ACP) in approved brand colors. The primary branding and logo are to be fabricated , internally illuminated with high-brightness, waterproof LED modules (IP65 rated) and powered by a matching branded SMPS power supply. Secondary text and taglines are to be executed using flat router-cut acrylic or premium outdoor-grade vinyl. The scope of work includes all internal concealed wiring, structural fasteners, scaffolding, and complete installation at the specified site elevation.	1.00	Nos	
	Total Amount			

Your Sealed quotations shall be reached this office within 7 (Seven) days from the date of issuing this letter. The Member Secretary, Maharashtra Pollution Control Board reserves the right to reject any or all quotations without giving any reason.

Terms & Conditions

1. Rates quoted shall be inclusive of all labour, materials, transportation, tools, taxes (excluding GST) and other incidental charges, unless specifically mentioned otherwise.

2. All materials used shall be of good quality and conform to applicable IS/BIS standards.
3. The work shall be completed as per the specifications and instructions of the authorized officer.
4. The contractor shall follow all applicable electrical safety rules and regulations.
5. Any defective work/material shall be rectified/replaced by the contractor at his own cost.
6. Payment shall be made after satisfactory completion and certification of the work.
7. GST will be paid at actual.
8. The decision of the competent authority regarding acceptance of the quotation shall be final.
9. The Member Secretary reserves the right to accept or reject any or all quotations without assigning any reason.

Digitally signed by
Bhalachandra Ramdas Jagtap
Date: 13-10-2026 14:42:40

(B. R. Jagtap)
Executive Engineer

Copy to – Chief Accounts Officer - 2, MPC Board, Sion, Mumbai – 400022.